

## जाहिर निविदा

शहर अभियंता, पनवेल महानगरपालिका हद्दीतील खारघर सेक्टर- 10 प्लॉट क्र 251 वर सामाजिक सभागृह बांधणे या कामाचे अंदाजपत्रक बनविण्याकरीता खाली नमूद केलेल्या बाबींकरीता दर मागविण्यात येत आहे.

अ. क्र.	कामाचे नाव	मुदत
१	पनवेल महानगरपालिका हद्दीतील खारघर सेक्टर- 10 प्लॉट क्र 251 वर सामाजिक सभागृह बांधणे.	23 / 8 / 2024 ते 30 / 8 / 2024 (७ दिवस)

### Specifications

Sr.No	Description	Quantity	Unit
1	Providing and fixing Laminate Finished <b>SLIDING FOLDING PARTITION</b> Operable Partition / Sliding Folding Partition ECOLITE - W100 consisting of series of individual flat elements of ZILIO make, 100 mm thick travelling along the ceiling track assembled to form a solid wall. The entire system must function as a solid wall and even when closed should reveal minimal screws, fixing or other similar solid metal parts. The sound insulation of the operable partition should be 47db tested under third party reputed laboratory in accordance to EN 20140-3. The test certificate should show the make and model of the system Construction :- Elements must be constructed of a torsion-free steel horizontal tube frame and torsion-stiff vertical profiles, bolted together to make the element strong and sturdy. The frame must be clad either side with 12mm MDF panels laminate finish hung in acoustic free suspension from the panel frame. The element must be constructed in accordance with the specified sound insulation requirements. The elements must be inter-connected by means of a positive locking concave/convex aluminium profile with an integrated magnetic strip and sealing lip having a linear attraction of 40N/m. The spindle mechanism in every element should be connected to the top and bottom horizontal seals which should be constructed of aluminium plates with flexible rubber at the contact point. Specially formed polyurethane corner rubber seal to be provided for overlapping acoustic seals horizontal sealing strip, as per manufacturer's specifications, etc. complete. Mode of measurements:- Front Elevation, one side only. (Sliding folding Partition Size 10.61x3.6m - 3nos.)	115	Sqm.
2	Providing and fixing heavy duty inter locking concrete Dark Grey Zig Zag ECO Pavers of 60 mm thickness <b>made of recycled silica and plastic mix</b> as per proprietary mix and having a strength of 500 Kilogram/Sq.cm. of approved quality and shape on a bed of crushed sand of 25 to 30 mm thick including skirting joints and cleaning etc. complete.	435	Sqm.
3	Design, Supply & fixing <b>Art Work Graphics Mural</b> on Life achievement & Pictorial biography of Shri D. B. Patil, in Entrance Lobby, Wall size: Length – 7 Meter x Height - 2.5 Meter as per Architects approvals, instruction including all required hardware, accessories, tool, fastners etc complete.	1	Nos.

4	Design, Supply & fixing <b>Art Work Mural with</b> respect to above item on Front External Elevation Wall size: Length – 9.0 Meter x Height - 4.0 Meter at Community center at Kharghar, mural shall be weather proof and partly backlighted with the help of outdoor lighting arrangements, Brass and copper shall be used along with steel to highlight various elements of the mural , as per Architects approvals, instructions, including all required hardware, accessories, tool, anchor fastners, scaffolding etc complete.	1	Nos.
---	---	---	------

वर नमूद सुचित दर्शविलेल्या बाबींचे पुरवठा करणारे पुरवठादार/दुकानदार/उत्पादक/विक्रेते यांनी नमूद केलेल्या बाबींकरीता असलेले दर स्वतःच्या लेटरहेडवर महापालिकेच्या कार्यालयात अथवा ई-मेल द्वारे [pmcbandhkamdept01@gmail.com](mailto:pmcbandhkamdept01@gmail.com) यावर दिनांक 30/04/2024 पर्यंत पाठवावे ही विनंती, सदर दर हे अंदाजपत्रक तयार करणेसाठी गृहित धरणेत येणार आहेत.



कार्यकारी अभियंता  
पनवेल महानगरपालिका

जा.क्र पमपा/बांधकाम/६५२४/प्र.क्र.३८/३१५९/२०२४  
दि. २३/०८/२०२४

प्रत माहितीस्तव —

१. प्रसिध्दीकरीता
२. माहिती फलक करीता