



पनवेल महानगरपालिका ता. पनवेल जि.रायगड



कार्यालय- आयुक्त मुख्यालय, २ रा मजला , देवाळे तलावाच्या समोरच, गोखले हॉलच्या शेजारी, पनवेल- ४१०२०६ दुरध्वनी क्र- ०२२-७४५८०४०/४१/४२
Email Id: panvelcorporation@gmail.com

जा.क्र. पमपा /विद्युत/२०२५/प्र.क्र.०२/४५९/

दिनांक-२०/०५/२०२५

जाहिर निविदा दरपत्रक सुचना

मा. आयुक्त, पनवेल महानगरपालिका खालील नमूद कामाचे अंदाजपत्रक बनविण्याकरीता खालील बाबींचे दर मागविण्यात येत आहे.

अ.क्र.	कामाचे नाव	कालावधी
१.	पनवेल महानगरपालिका क्षेत्रामधील खारघर रेल्वे स्टेशनला लागून असलेला स्कॉयवॉक वर पारेषण संलग्न ६३० KWp (On Grid) क्षमतेचा सौर ऊर्जा संच स्थापित करून कार्यान्वित करणे.	दिनांक- २१/०५/२०२५ ते दिनांक-२७/०५/२०२५ (७ दिवस)


तपशिल

अ.क्र.	तपशिल	परिमाण	युनिट
१.	Supplying, installing, testing and commissioning of 630 kWp ON-GRID Solar PV System / Plant consisting Solar PV Mono Crystalline Panel 540 Wp X 1167 Nos.) and Solar ON-GRID Inverter of similar capacity (THD<3%) with interconnecting wires/cables up to solar ON GRID inverter, proper base plate, canopy box to house Inverter and necessary accessories .e. ACDB/ DCDB ,MCB etc. wiring up to solar Inverter in conduit, display board, sign board, two distinct earthing, lightning arrester, remote monitoring system with maintaining card/ chip for 5 years including charges for RMS Systemn, net complete up to net meter Installation and export to the grid with 5 year ON-SITE warranty and fully comprehensive maintenance contract as per Specification.The work also includes providing and erecting synchronisation Panel to transmitting AC power supply generated through solar Plant.	१	wp
२	MSEDCL Net Metering application Fees, Energy Meter cost - Net Meter/ABT Meter and Solar Generation meter (CT PT and meters procurement as per MSEDCL Specifications, Meter testing,	१	job

	installation and testing, etc.), cabling from inverter to net metering including all accessories.		
३	Providing & erecting lifeline and walkway of required Market Rate length/width as per site requirements with support and accesserioes for necessary saftey Precations.	१	wp
४	Supplying, installing, testing and commissioning conventional type Lightning Arrestor including Earthing Cable, Earthing kit and Earthing cable for LA	१	Each
५	Distribution Panel-Supplying, Erecting and distribution panel with necessary switchgear, load Manager, wiring & allied accessories as prevailing standards as per the rating of connected Load including foundation and fencing.	१	Job
६	Main Panel-Supplying, erecting and distribution Panel with necessary switchgear. load Manager, wiring & allied accessories as prevailing standards as per the rating of connected Load and capable for generating of 650 kwp including foundation and fencing.	१	job

अटी व शर्ती :-

१. सीलबंद दरपत्रके दिनांक-२१/०५/२०२५ ते दि. २५/०५/२०२५ रोजीपर्यंत दुपारी ३.०० वाजेपर्यंत पनवेल महानगरपालिकेच्या विद्युत विभागात किंवा pmcelectrical123@gmail.com या ई-मेलवर स्वीकारण्यात येतील.
२. सदरचे दरपत्रक हे अंदाजपत्रक बनविण्यासाठी असून सदर कामांवर Manufacturer/Dealer/Contractor चा दावा (Claim) असणार नाही.
३. Manufacturer/Dealer/Contractor ने दिलेले दरपत्रक स्विकारणाचे सर्व अधिकार पनवेल महानगरपालिकेकडे असतील याची नोंद घ्यावी.


प्रतिक पाटील
 विद्युत विभाग प्रमुख
 पनवेल महानगरपालिका

प्रत माहितीस्तव :-

१. माहिती फलककरीता