

पनवेल महानगरपालिका जाहीर निविदा दरपत्रक

आयुक्त,पनवेल महानगरपालिका हद्दीतील प्रभाग समिती-ड, प्रभाग क्र.१९ मधील अंतिम भूखंड क्र.५०६ कोळीवाडा मार्केट यार्ड परिसरातील स्मशानभूमी विकसीत करणे. या कामाचे अंदाजपत्रक बनविण्याकरीता खालील नमूद केलेल्या बाबीकरीता खालील नमूण्यात दर मागविण्यात येत आहे.


अ.क्र.	कामाचेनाव	मुदत
१	पनवेल महानगरपालिका हद्दीतील प्रभाग समिती-ड, प्रभाग क्र.१९ मधील अंतिम भूखंड क्र.५०६ कोळीवाडा मार्केट यार्ड परिसरातील स्मशानभूमी विकसीत करणे.	०५/०८/२०२५ ते २२/०८/२०२५ (७ दिवस)

Specification

Sr. No	Item	Includes	DESCRIPTION	Quantity	Unit
1.	SITC of Flaps around the pyre . MD Steel, HR painted. 3000 x 914 x 5 mm	Flaps around the pyre hood	Metallic flaps around the pyre hood which can be manually lowered to reduce lateral escape of smoke and particulate matter	1	Set
2.	SITC of Air Purification System	A. Dust Vortex System	Separates out particulate matter higher than and up to PM 10.	1	Unit
		B. Electrostatic Precipitator (ESP)	Collection of PM10 & PM 2.5 on collector plates-ensuring cleaner emissions.		
		C. Vapox	Removes oils, chemicals, and toxic fumes - cutting down hazardous emissions		
		D. IOT data Monitoring	Continuous data monitoring system which indicates the inlet gas parameters and outlet parameters, which enables us to check the health of the treatment system, its efficiency and the cleaning indicators.		
		E. ETP	A water treatment system for our unit which ensures no air pollution is converted into water pollution, the water can be reused into the system or for gardening / cleaning purposes.		
		F. High Capacity Blower	A 15,000 CFM blower which will Ensure no pressure drop in the system as well as finest of particles are taken into the cleaning system by the hood.		
3.	SITC of modification of existing site with RMT 35 of main ducting interconnecting to hoods, Dampers,	H. Modification and installation of the APC on site.	SITC of integrating the Airpurification system with the existing system present at the crematorium.	1	Set

	Blower/ exhaust fan assembly				
4.	NABL Testing	NABL lab Air sampling and testing	NABL certified testing of inlet & outlet parameters before and after air purification.	1 Pre + 1 Post Treatment Analysis	Job

वर नमूद सुचित दर्शविलेल्या बाबींचे पुरवठा करणारे पुरवठादार/दुकानदार/उत्पादक/विक्रेतेयांनी नमूद केलेल्याबाबींकरीता असलेले दर स्वतःच्या लेटर हेड वर महापालिकेच्या कार्यालयात अथवा ई-मेलद्वारे pmcbandhkamdept01@gmail.com या वर दिनांक ०४/०८/२०२५ पर्यंत पाठवावे ही विनंती, सदर दर हे अंदाजपत्रक तयारकरणेसाठी गृहित धरणेत येणारआहेत.



कार्यकारी अभियंता
पनवेल महानगरपालिका

जा.क्र.पमपा/बांधकाम/प्र.क्र./ २६२५/२०२५,
दि. ०४/०८/२०२५

प्रतमाहितीस्त्व - १. माहितीफलककरीता